

Form of Tender: Pricing

The Contractor hereby states that the following unit prices shall constitute full compensation for the works specified under the contract. Unit prices and amounts, subtotals, and totals must not include HST.

ITEM						
NO.	SP	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
1.0		General Work				
1.01	14	Mobilization & Demobilization	LS	1		
1.02	15	Traffic Control & Signage	LS	1		
1.03	16	Environmental Protection	LS	1		
1.04	17	Business & Pedestrian Disruption Mitigation & Communication	LS	1		
		Subtotal General Work				
2.0		Removals				
2.01	18	Remove, Store and Reinstall Park Signage (Provisional)	ea	1		
2.02	18	Remove, Store and Reinstall Park Bench	ea	7		
2.03	18	Remove, Store and Reinstall Waste & Recycling Receptacle	ea	2		
2.04	19	Remove and Dispose of Timber Park Benches Inside Gazebo	LS	1		
2.05	20	Remove and Dispose of Existing Unit Pavers	m ²	180		
2.06	21	Earth Excavation & Grading	m ³	90		
		Subtotal Removals				
3.0		Electrical Works				
3.01	22	Remove, Replace and Modify Electrical Elements in Parkette	LS	1		
4.0		Walkway and Drainage Improvement Works				
4.01	23	Construct 150mm Thick Decorative Patterned Concrete Walkway on Granular Base and Subbase	m ²	180		

4.02	24	Supply and Install 150mm Dia. Perforated Subdrain in Clear Stone Wrapped in Filter Fabric	m	45
4.03	24	Construct French Drain with 150mm Dia. Perforated Subdrain in Riverstone and Filter Fabric	m	15
4.04	25	Supply and Install Drain Basin c/w 600mm Deep Sump and Subdrain Connection	ea.	1
4.05	26	Core and Connect 150mm Dia. Subdrain to Existing Double Catch Basin	ea.	1
4.06	27	Regrading and 100mm Depth Topsoil and Sod	m ²	165
Subtotal Walkway and Drainage Improvement Works				
5.0	Contingency			
5.01	28	Allowance Contingency	Allow	\$10,000
Subtotal Contingency				
Total				

Definitions:

SS – Supplementary Specifications

(P) – Plan Quantity Measurement and Payment

ea. – Each, t – Tonne, kg – Kilogram, LS – Lump Sum

m – Linear Metre, m² – Square Metres, m³ – Cubic Metres, Allow - Allowance

Warranty:

The issuing of the final payment shall not relieve the Contractor from responsibility for faulty material or workmanship appearing in the work within one (1) year from the date of acceptance of the work by the Contract Administrator.

The Contractor guarantees that the said work shall remain in such condition as will meet with the approval of the Contract Administrator and that he will, upon being required by the Contract Administrator, make good in a permanent manner, any imperfections therein due to materials or workmanship used in the construction thereof.

In the first instance the Contract Administrator shall decide the nature and cause of such imperfections and the necessity for remedying the same. Should the Contractor fail to comply with the directions to correct such deficiencies, the Contract Administrator, after giving the Contractor 12 hours written notice or such other reasonable time as approved,

Optional Provisional Items

6.0		Provisional Items		
6.01	29	Sub-Excavate, Remove & Replace of Unsuitable Subgrade Material	m ³	10
6.02	30	Supply and Place Select Subgrade Material	t	20
6.03	31	Granular A	t	40
Subtotal Provisional Items				

This addendum is issued as part of "Contract: CTY-MH-2024-2".

Name of Bidder: _____

Signature of Bidder : _____

Date: _____

End of Addendum No. 3