



May 30, 2023

Addendum #4

for RFT RDS 23-002

Reconstruction of Bobcaygeon and Scotch Line Roads

This addendum shall be incorporated into and form part of RFT #RDS 23-002 for the reconstruction of Bobcaygeon and Scotch Line Roads.

Please see attached updated quantities.

Receipt of the Addendum shall be acknowledged as part of your submission as per Section 2.14 – Addenda of the RFT document and **must be included** in the submission package before the closing date of **June 2, 2023 at 12:00 noon**.

The Township of Minden Hills reserves the right to reject any or all Tenders or accept any Proposal, should it deem such actions to be in the best interest of the Township.

Additional questions will be addressed in a coming addendum.

Questions that have not yet been submitted may not be answered.

This addendum consists of 1 page and an updated quantity file package.

If you have questions regarding this matter, please contact the Township directly as outlined in Section 2.13 – Inquiries of the RFT document.

Sincerely,

Mike Timmins
Director of Public Works

Acknowledgement of Receipt

Bidders are required to acknowledge receipt of all addenda by signing the Acknowledgement of Receipt below. Failure to submit all addenda will constitute an automatic rejection.

I/we hereby acknowledge receipt of this addendum and make allowances in my bid.

Signature of Bidder

Date

Name of Company

Appendix F - Price & Delivery Schedule

****MANDATORY COMPLETION****

The Respondent hereby states that the following unit prices shall constitute full compensation for the works specified under the Contract:

Bobcaygeon Road

SECTION 1 – Site Preparation, Removals, Erosion Control						
Item No.	Spec. No.	Description of Item	Est. Qty.	Unit	Unit Price	Total Price
1.01	SP	Insurance and Bonding	1	LS	\$	\$
1.02	SP	Mobilization / Demobilization	1	LS	\$	\$
1.03	805, SP	Erosion & Sediment Control (silt fence, check dams, ongoing maintenance)	1	LS	\$	\$
1.04	203,301,314, 330,501 SP	In-Place Processing	20615	m ²	\$	\$
1.05	180, 510	CSP Culvert Removal	196	m	\$	\$
1.06	206, SP	Ditching	6000	m	\$	\$
1.07	180, 206	Strip and Export Topsoil	16250	m ²	\$	\$
1.08	180, 206, 501 SP	Earth Excavation	2310	m ³		
1.09	201, SP	Tree Clearing and Grubbing	1	LS	\$	\$
1.10	706, SP	Traffic Control	1	LS	\$	\$
TOTAL SECTION NO.1: (excluding HST)						\$

SECTION 2 – Storm Sewer						
Item No.	Spec. No.	Description of Item	Est. Qty.	Unit	Unit Price	Total Price
2.01	421,SP	375mm HDPE Driveway Culverts (Driveways -14)	169	m	\$	\$
2.02	421,SP	450mm HDPE Driveway Culverts (Driveways - 17)	155	m	\$	\$
2.03	421,SP	375mm HDPE Cross Culverts incl. frost taper	25	m	\$	\$
2.04	421, SP	450mm HDPE Cross Culverts incl. frost taper	52	m	\$	\$
TOTAL SECTION NO.2: (excluding HST)						\$

SECTION 3 – Road Construction						
Item No.	Spec. No.	Description of Item	Est. Qty.	Unit	Unit Price	Total Price
3.01	314, 501,1001, SP	Granular 'A' (150mm depth)	9,700	t		
3.02	314, 501,1001, SP	Granular 'A' Driveways (150mm depth)	600	t		
3.03	314, 501,1001, SP	Granular 'A' Platform Widening	750	t		
3.04	314, 501,1001, SP	Granular 'B' Platform Widening (450mm depth)	4,300	t		
3.05	314, 501,1001, SP	Shouldering	3,900	m ²		
3.06	314, 501,1001, SP	Import SSM	1000	t		
3.07	310,1003,11 50,1101, SP	Hot Mix HL1 PG58-34 Asphalt (50mm depth)	20615	m ²		
3.08	310,1003,11 50,1101, SP	Hot Mix HL3 PG58-34 Asphalt (50mm depth) (Driveway)	20	m ²		
3.09	802, 804, SP	Topsoil (100mm) and Hydroseeding	15000	m ²		

TOTAL SECTION NO.3: (excluding HST)	\$
--	-----------

Bobcaygeon Road Summary	
Total Section No. 1 - Site Preparation, Removals, Erosion Control	\$
Total Section No. 2 – Storm Sewer	\$
Total Section No. 3 – Road Construction	\$
Sub-total Tender (excluding HST)	
HST@ 13%	\$
Total Tendered Price	\$

Scotch Line Road

SECTION 4 – Site Preparation, Removals, Erosion Control						
Item No.	Spec. No.	Description of Item	Est. Qty.	Unit	Unit Price	Total Price
4.01	SP	Insurance and Bonding	1	LS	\$	\$
4.02	SP	Mobilization / Demobilization	1	LS	\$	\$
4.03	805, SP	Erosion & Sediment Control (silt fence, check dams, ongoing maintenance)	1	LS	\$	\$
4.04	203,301,314, 330,501 SP	In-Place Processing	15660	m ²	\$	\$
4.05	180, 510	CSP Culvert Removal	188	m	\$	\$
4.06	206, SP	Ditching	4000	m	\$	\$
4.07	180, 206	Strip and Export Topsoil	9320	m ²	\$	\$
4.08	180, 206, 501 SP	Earth Excavation	2090	m ³		
4.09	201, SP	Tree Clearing and Grubbing	1	LS	\$	\$
4.10	706, SP	Traffic Control	1	LS	\$	\$
TOTAL SECTION NO.1B: (excluding HST)						\$

SECTION 5 – Storm Sewer						
Item No.	Spec. No.	Description of Item	Est. Qty.	Unit	Unit Price	Total Price
5.01	421,SP	375mm HDPE Driveway Culverts (Driveways – 28)	272	m	\$	\$
5.02	421,SP	600mm HDPE Driveway Culverts (Driveways - 1)	14	m	\$	\$
5.03	421,SP	375mm HDPE Cross Culverts incl. frost taper	18	m	\$	\$
5.04	421, SP	450mm HDPE Cross Culverts incl. frost taper	14	m	\$	\$
5.05	421,SP	600mm HDPE Cross Culverts incl. frost taper	17	m	\$	\$

5.06	421,SP	1800mm HDPE Cross Culverts incl. frost taper	60	m	\$	\$
------	--------	---	----	---	----	----

TOTAL SECTION NO.5: (excluding HST)	\$
--	----

SECTION 6 – Road Construction						
Item No.	Spec. No.	Description of Item	Est. Qty.	Unit	Unit Price	Total Price
6.01	314, 501,1001, SP	Granular 'A' (150mm depth)	9,000	t	\$	\$
6.02	314, 501,1001, SP	Granular 'A' Driveways (150mm depth)	650	t	\$	\$
6.03	314, 501,1001, SP	Granular 'A' Platform Widening	750	t	\$	\$
6.04	314, 501,1001, SP	Granular 'B' Platform Widening (450mm depth)	3,450	t	\$	\$
6.05	314, 501,1001, SP	Shouldering	1,600	m ²	\$	\$
6.06	314, 501,1001, SP	Import SSM	1000	t	\$	\$
6.07	310,1003,11 50,1101, SP	Hot Mix HL1 PG58-34 Asphalt (50mm depth)	18270	m ²	\$	\$
6.08	310,1003,11 50,1101, SP	Hot Mix HL3 PG58-34 Asphalt (50mm depth) (Driveways)	540	m ²	\$	\$
6.09	802, 804, SP	Topsoil (100mm) and Hydroseeding	10000	m ²	\$	\$
TOTAL SECTION NO.3B: (excluding HST)						\$
Scotch Line Road Summary						
Total Section No. 4 - Site Preparation, Removals, Erosion Control					\$	
Total Section No. 5 – Storm Sewer					\$	
Total Section No. 6 – Road Construction					\$	

Sub-total Tender (excluding HST)	
HST@ 13%	\$
Total Tendered Price	\$

Tender Summary		
Total – Bobcaygeon Road (A)		\$
Total – Scotch Line Road (B)		\$
Sub-total Tender (excluding HST)		
HST# _____	HST@ 13%	\$
Total Tendered Price (Bobcaygeon and Scotch Line)		\$

Provisional:

Tender award will be made based upon the lowest compliant bidder for the Total Tendered Price. Once the lowest compliant bidder has been identified the Township reserves the right to include any or all of the provisional items at any time during the award or construction process.

SECTION 7 – Provisional Items						
Item No.	Spec. No.	Description of Item	Est. Qty.	Unit	Unit Price	Total Price
7.01	201, SP	Remove and Dispose of Existing Boulders	20	m ³	\$	\$
7.02	421,SP	375mm CSP -Driveway Culverts	441	m	\$	\$
7.03	421,SP	450mm CSP – Driveway Culverts	155	m	\$	\$
7.04	421,SP	600mm CSP – Driveway Culverts	13	m	\$	\$
7.05	310,1003,1150,1101, SP	Asphalt Gutter	200	m	\$	\$
7.06	SP	Pre-Construction Survey	1	LS	\$	\$
7.07	SP	Granular Sealing	5,500	m ²	\$	\$
7.08	SP	Rip Rap w/ Geotextile	800	m ²	\$	\$