

April 2, 2026

**Addendum #2
for RFP No. RDS 26-001
Clear Lake Road Twin Culverts**

This addendum shall be incorporated into and form part of RFP No. RDS 26-001 for the replacement of the Clear Lake Road Twin Culverts.

Receipt of the Addendum shall be acknowledged as part of your submission as per Section 2.14 – Addenda of the RFP document and **must be included** in the submission package before the closing date of April 10, 2026 at 12:00 noon.

The Township of Minden Hills reserves the right to reject any or all tenders or accept any proposal, should it deem such actions to be in the best interest of the Township.

In addition to the questions below, please review the revised Appendix G – Price & Delivery Schedule as there have been some minor changes for clarify.

Question 1: What material is to be used for backfill?

Answer 1: The backfill is to be native material, if suitable. If the native material is found to be unsuitable backfill material, a provisional item for Granular B backfill has been included in the bid form, Item 3.05.

Question2: Inside the pricing tables included with the tender, it indicates Granular B - can you confirm if this is to be granular B type 1 or type 2.

Answer 2: Granular B Type 1 and Type 2 will both be accepted.

Question 3: Please specify diameter size for crushed rock which is located under the culvert bedding material.

Answer 3: The crushed rock will be 50mm-100mm. See added Item 2.13.

Question 4: Please confirm Item 3.02 is to be completed with rock blasting or by mechanical means.

Answer 4: If rock excavation is required, it is expected to be minimal, and mechanical excavation is expected to suffice. Please see updated Item 3.02.

This addendum consists of seven (7) pages, including revised Appendix G – Price & Delivery Schedule.

If you have questions regarding this matter, please contact the Township directly as outlined in Section 2.13 – Inquiries of the RFP document.

Sincerely,

Mike Timmins
Director of Public Works

Acknowledgement of Receipt

Bidders are required to acknowledge receipt of all addenda by signing the Acknowledgement of Receipt below. Failure to submit all addenda will constitute an automatic rejection.

I/we hereby acknowledge receipt of this addendum and make allowances in my bid.

Signature of Bidder

Date

Name of Company

6.7 Appendix G - Price & Delivery Schedule REVISED April 2, 2026

****MANDATORY COMPLETION****

(All unit prices are not to include H.S.T.)

The undersigned contractor agrees to supply and deliver the goods and services as specified and required in accordance with the Tender Documents, Drawings and Ontario Provincial Standard Specification for the following prices:

The Owner reserves the right to cancel any or all items.

SECTION NO. 1 – Site Preparation, Removals and Erosion Control						
ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
1.01	100	Insurance and Bonding	LS	1	\$ _____	\$ _____
1.02	100	Mobilization & Demobilization	LS	1	\$ _____	\$ _____
1.03	100	Layout & As-Builts	LS	1	\$ _____	\$ _____
1.04	706	Traffic Control	LS	1	\$ _____	\$ _____
1.05	805	Light Duty Silt Fence	m	86	\$ _____	\$ _____
1.06	182, 805	Turbidity Curtain	m	19	\$ _____	\$ _____
1.07	182, 805	Coffer Dams	LS	1	\$ _____	\$ _____
1.08	182, 517	Dewatering (Pump & Outlet Sediment Bag)	LS	1	\$ _____	\$ _____
1.09	201	Clearing & Grubbing	LS	1	\$ _____	\$ _____
1.10	206, 510	Strip & Export Topsoil	m ²	170	\$ _____	\$ _____
1.11	510	Remove Existing Gravel Shoulder	m ²	60	\$ _____	\$ _____
1.12	510	Remove Existing Asphalt (Full Depth)	m ²	260	\$ _____	\$ _____
1.13	510	Remove Existing 1600mm CSP Culverts	m	48	\$ _____	\$ _____

--	--	--	--	--	--	--

SECTION NO. 1 – Site Preparation, Removals and Erosion Control

ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
1.14	720, 722, 913.220, 913.255	Remove, Salvage & Reinstall Ex. Standard 3 Cable Guide Rail	LS	1	\$ _____	\$ _____
1.15	180, 206	Earth Excavation	LS	1	\$ _____	\$ _____
1.16	182, 805	Maintenance of Erosion & Sediment Control	LS	1	\$ _____	\$ _____
TOTAL SECTION NO. 1: (excluding HST)						\$ _____

SECTION NO. 2 – Site Construction

ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
2.01	314, 501	Granular 'A' (150mm depth)	m ²	260	\$ _____	\$ _____
2.02	314, 501	Granular 'B' (300mm depth)	m ²	260	\$ _____	\$ _____
2.03	310	Hot Mix HL3 - Surface Asphalt (40mm depth)	m ²	272	\$ _____	\$ _____
2.04	310	Hot Mix HL8 - Base Asphalt (50mm depth)	m ²	260	\$ _____	\$ _____
2.05	314, 501	Gravel Shoulder / Parking Bump Out (200mm depth)	m ²	60	\$ _____	\$ _____
2.06	401, 410, 421	1600mm Ø CSP Culvert 2.8mm minimum thickness	m	48	\$ _____	\$ _____
2.07	511	300mm Ø Rip Rap (450mm depth)	m ²	53	\$ _____	\$ _____

SECTION NO. 2 – Site Construction

ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
2.08	511	300mm Ø Riverstone (300mm depth)	m ²	44	\$ _____	\$ _____
2.09	802, 804	Topsoil and Seed (150mm depth)	m ²	170	\$ _____	\$ _____
2.10	180, 510	Provisional Item: Disposal of contaminated soil	LS	1	\$50,000	\$50,000
2.11	206, 401, 501	Backfill with native materials	m ³	270	\$ _____	\$ _____
2.12	511, 1860	19mm Ø Clear stone Bedding wrapped with Geotextile	m ³	38	\$ _____	\$ _____
2.13	511, 1860	50-100mm Ø Crushed Rock wrapped with Geotextile	m ³	50	\$ _____	\$ _____
TOTAL SECTION NO. 2: (excluding HST)						\$ _____

Bid Summary	
Total Section No. 1 – Site Preparation, Removals and Erosion Control	\$ _____
Total Section No. 2 – Site Construction	\$ _____
Sub-total Tender (excluding H.S.T)	\$ _____
HST # _____ HST @ 13%	\$ _____
Total Tendered Price (basis of award)	\$ _____

Provisional:

SECTION NO. 3 – Provisional Items						
ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
3.01	720, 722, 913.220, 913.255	Install New Metal Post for High Tension Cable Guide Rail	ea.	5	\$ _____	\$ _____
3.02	202, 403	Rock Excavation, mechanical	m ³	10	\$ _____	\$ _____
3.03	802, 805	Erosion Control Blanket	m ²	20	\$ _____	\$ _____
3.04	578	Unshrinkable Backfill (U-Fill)	m ³	24	\$ _____	\$ _____
3.05	206, 401, 501	Backfill with Granular 'B'	m ³	270	\$ _____	\$ _____
TOTAL SECTION NO. 3: (excluding HST)						\$ _____