

SECTION NO. 1 – Site Preparation, Removals and Erosion Control

ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
1.01	100, SP	Insurance and Bonding	LS	1	\$ _____	\$ _____
1.02	100, SP	Mobilization & Demobilization	LS	1	\$ _____	\$ _____
1.03	706, SP	Traffic Control / Pedestrian Access	LS	1	\$ _____	\$ _____
1.04	805, SP	Environmental Considerations	LS	1	\$ _____	\$ _____
1.05	510, SP	Concrete Sidewalk Removal, incl. granular/earth removal to subgrade at approx. 140 locations	m ²	1275	\$ _____	\$ _____
1.06	510, SP	Concrete Curb Removal, incl. granular/earth removal to subgrade	m	50	\$ _____	\$ _____
TOTAL SECTION NO. 1: (excluding HST)						\$ _____

SECTION NO. 2 – Surface Works

ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
2.01	206, 314, 351, 501, 1001, 1002, 1010, 1350, SP	125mm Concrete Sidewalk (varying widths), incl. 150mm Granular 'A' at approx. 140 locations	m ²	1275	\$ _____	\$ _____
2.02	206, 314, 353, 501, 1001, 1002, 1010, 1350, SP	Concrete Curb (all styles)	m	230	\$ _____	\$ _____
TOTAL SECTION NO. 2: (excluding HST)						\$ _____

Bid Summary

Total Section No. 1- Site Preperation, Removals and Erosion Control

\$ _____

Total Section No. 2- Surface Works

\$ _____

Sub-Total (Excluding HST)

\$ _____

HST # _____

HST @ 13%

\$ _____

Total Tender Price (basis of Award)

\$ _____

SECTION NO. 3 – Provisional Items

ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
3.01	206, 510	Sub-Excavate due to poor soil conditions	m ³	25	\$ _____	\$ _____
3.02	510, SP	Asphalt Removal (full depth)	m ²	75	\$ _____	\$ _____
3.03	206, 501, 1001, 1010	Imported SSM to Subgrade	t	50	\$ _____	\$ _____
3.04	206, 310, 314, 501, 1001, 1003, 1010	Hot Mix HL8 - Base Asphalt (50mm depth), incl. 150mm Granular 'A'	m ²	72	\$ _____	\$ _____
3.05	310, 501, 1003	Hot Mix HL3 - Surface Asphalt (50mm depth)	m ²	75	\$ _____	\$ _____
3.06	510	Saw Cut Straight Lines for Asphalt Transition	m	120	\$ _____	\$ _____
3.07	351	Tactile Walking Surface Indicator Plates	ea	30	\$ _____	\$ _____
3.08	802, 804	Topsoil and Seed (150mm depth)	m ²	50	\$ _____	\$ _____
TOTAL SECTION NO. 3: (excluding HST)						\$ _____